



Request for Quote: Drywall Services

Vendor Search Dates: Start: March 25, 2022

Good morning,

We are soliciting quotes from qualified persons or companies to provide Drywall Installation, labor only. We are a tax exempt organization which should be taken into account for this proposal. This scope is for five (5) single family residential projects (listed below) located in Paterson, NJ. Once written request is received, we ask that all proposals are **submitted within 10 business days**. Any questions regarding this proposal can be sent to Rob Alvarado, Construction Director, Paterson Habitat for Humanity, via email: rob@patersonhabitat.org or call the office: **973-595-6868 ext. 114**, or Diomedes Vargas , Project Coordinator, via email: Dee@patersonhabitat.org or call, **ext. 122**.

Address:

1. 142 governor st
2. 144 governor st
3. 146 governor st
4. 148 governor st
5. 150 governor st

Scope of Work at each location:

- Labor and Installation guideline for Standard Unit:
 - First Floor/Garage
 - Exterior Walls 5/8" Sheetrock
 - Interior Walls 5/8" Sheetrock
 - Ceiling (double layer) 5/8" Sheetrock

Caulk seal all seams between layers
 - Second Floor/ Living Room/Kitchen
 - Exterior Walls 5/8" Sheetrock
 - Interior Walls 5/8" Sheetrock
 - Ceiling (Double layer) 5/8" Sheetrock

Caulk seal all seams between layers
 - Third Floor/Bedrooms
 - Exterior Walls 5/8" Sheetrock
 - Interior Walls 5/8" Sheetrock
 - Ceiling (double layer) 5/8" Sheetrock

Caulk seal all seams between layers
 - Two Master Bathroom Walls
 - 5/8" Tile Backer around tub
 - 5/8" Mold resistant Sheetrock
- Materials to be provided and loaded by PHFH per level/location (confirm number with contractor before or):
 - Garage Level
 - 4X12 Sheetrock fire 5/8" @ (#41258FC) Total: 60 Sheets
 - Blue 4.5 Gal. Lite weight Spackle Total: 18 Count

- Green 4.5 Gal. all-purpose Spackle Total: 8 Count
- Sheetrock Joint Tape 2-1/6" x 250' Total: 20 Rolls
- 1-1/4" x 8' Corner Bead 63 PCS/box Total: 63 Pieces
- Course Thread Screws 6 x 1-1/4" 8M Total 3 Boxes
- Course Thread Screws 6 x 2 Bulk 3.5M Total 2 Boxes
- Course Thread Screws 6 x 3 Bulk 3.5M Total 3 Boxes
- Fine thread Bulk 8 x 2-1/2" 2.5M Total 1 Box
- Second Floor
 - 4 x 12' x 5/8" Sheetrock fire code (#41258FC) Total 52 Sheets
 - Cement Board 4 x 8' x 5/8" Total 3 Sheets
 - 4 x 12' x 5/8" mold and moisture board Total 4 Sheets
- Third Floor
 - 4 x 12' x 5/8" Sheetrock fire code (#41258FC) Total 57 Sheets
 - Cement Board 4 x 8' x 5/8" Total 3 Sheets
 - 4 x 12' x 5/8" mold and moisture board Total 4 Sheets

Clarifications:

- All Subcontractors must provide Liability Insurance, Worker Compensation, and complete our preapproval documents
- PHFH will provide onsite restroom
- PHFH will provide propane and heating station upon request
- PHFH will load all drywall prior to job start
- PHFH will clean all waste in the install phase and finish phase

Diomedes Vargas

Project Manager

Habitat for Humanity Paterson

Dee@patersonhabitat.org

973-595-6868 ext. 122